

Exhibit P-47

McGill University

DEPARTMENT OF BUILDINGS AND GROUNDS

DIVISION

ESTIMATE

To Dr. D. E. Cameron. Number Q-1826
 Department of Chairman.
 Building Psychiatry, A.M.I. ROYAL VICTORIA HOSPITAL
Department of Psychiatry Feb. 25th, 19 59.

DESCRIPTION OF WORK REQUESTED BY Dr. Boag.

Proposed Alterations to part of A.M.I. Stable to be used for Movie Photography.

- | | |
|---|----------|
| 1. Remove the partition and existing floor of the carpenters shop. | \$ 15 00 |
| 2. Install a plywood covered partition in the archway to the section at the rear which is now to be the carpenters shop.
Size of partition, 11'2" x 8'0". | 53 00 |
| 3. Repair the existing entrance doors and make weather proof. Slide the doors open 3'3" in the centre, supply and install a door and frame between the existing doors. | 64 00 |
| 4. Supply and install a floor over the existing tile, consisting of 2" x 4" spruce plates fixed level and secured to the existing floor, 2" x 4" joists to be securely fixed to the plates at 16" cts. with solid bridging every 4'0", 2" B.C. fir plywood to be fixed to the joist, size of floor 26'0" x 33'0" plus two sections 6'0" x 6'0".
This is larger than the rear room.
Size of rear room 25'6" x 30'6" plus a 5'0" x 5'0" triangle. | 568 00 |
| 5. Supply and install "A" Gauge Marbolem on the new plywood floor. | 511 |
| 6. As an alternative to the wooden floor, supply and install a concrete floor, level and bonded to the existing tile. \$372.00 | |
| 7. Supply and install asphalt tile on the new concrete floor. \$465.00
Linoleum is not good on a concrete floor that has no ventilation under it. | |
| 8. Alter the door to the furnace room to suit the new condition. | 7 |
| 9. Supply and install 6 Duplex 110V outlets on the west wall of the room. | 65 |
| 10. Remove the airconditioning unit from the west wall, make good the wall. | 21 |
| 11. Remove the existing curtain track from the rear section and reinstall in front section. | 10 |
| 12. Wash the glazed brick, paint the panels between the brick. | 50 |
| 13. Supply & install 7 background boards, consisting of 2" x 2" pine frames, morticed together & securely braced with a sheet of ten-test fixed on 1 side. Hooks & eyes to be installed to secure the frames to the wall when required. | 12 |

The work described above has been estimated on the basis of Buildings and Grounds cost of labor and materials as at to-day's date and cannot be started until a requisition is put through the proper channels and a "work order" approved by the Accounting Department.

Should a Faculty or Department require a change in specifications that will increase estimated cost, then changes must be approved in writing by the Accounting Department and the Department of Buildings and Grounds.

APPROVED:

B. Shepton
 FOR SUPERINTENDENT OF BUILDINGS AND GROUNDS